




E-XFEL STANDARD ELECTRON BEAM DIAGNOSTICS

Dirk Nölle for the XFEL Diagnostics Team

DEELS Workshop, ESRF, 12.05.2014



HELMHOLTZ
| ASSOCIATION





Outline

- Short Roundtrip of the XFEL Project
- What is the Standard Diagnostics?
- Beam Position Monitors (Collaboration with PSI/CEA)
 - This talk will show the aspects of the mechanics
- Charge Monitors
 - Toroids
 - Dark Current Monitors
- Beam Size Measurements
 - Screens
 - Wire scanners
- Beam Loss Monitors
- Dosimetry System
- Other ... Restriction of the Talk's Scope to "Main Systems"

Accelerator Layout


One injector initially installed

Connection to 2nd stage upgrade included in beam distribution layout




- 17.5 GeV superconducting LINAC
- RF photoinjector, two bunch compression stages
- 3 SASE undulators plus 1 spontaneous source, extension possible
- 5 experimental stations to be extended to 10
- potential extension with a second experimental hall


E-XFEL Time Structure: High Duty Cycle



- Repetition rate




- Macro-pulse



- Bunch




- Slice



- Up to 27000 Bunches/s

FLASH and E-XFEL have the same time structure




- Distribution of the electron beam in the beam switchyard
- Kicker septum scheme with precision kicker and septum + knock out kicker
 - Machine operated with fixed beam loading (only length of the train is varied)
 - 3 way switch
 - SASE 1
 - SASE 2
 - Dump
 - First bunches send to the dump (used for locking of feedbacks)
 - First half train is send to SASE 1
 - Second half train is send to SASE 2
 - Not needed bunches can be knocked out to the dump

- Civil Construction started 2009
- Christmas 2009: XFEL Company founded
- Underground Construction finished: 6/2013
- Infrastructure of XTL ready: 9/2013
- RF Test of Gun in the Injector Tunnel: Dec 2013
- Start of Machine Installation: now
- Commissioning of the Gun: Summer 2014
- Commissioning of the Injector: Spring 2015
- Installation Ready; Tunnel Closed: 7/2016
- First Lasing Possible: Dec 2016






Open Day for DESY Staff, Feb. 2012



2/2012

What a Vision!!! (same Position 3/2014)






More Pictures from the XFEL Project:


<http://xfel.desy.de/pictures/>

http://adweb.desy.de/home/dnoelle/WWW/XFEL_meets_Photoshop/index.html

What is Standard Diagnostics at XFEL?




System	Subsystem	Gun	Injektor [XTIN]	XTL	XTDs
BPM System ~ 480	Button	1	16	180	111
	BPME				101
	BPMF/I		3	19	5
	BPMR		1	30	
	Button Array			3	
	HOM		2		
Charge ~ 50	FCUP	3			
	DCM	1	1	8	
	Toroid	1	3	16	15
Screens ~ 75	Simple	3			
	OTR_ABCL		7	26	16
	OTR_DE		1	4	5
	OTRS			3	
	Beam Size Dump			1	2
Wire Scanners 12				6	6
Loss Monitors ~ 320	BLM	1	18	100	192
	BHM		1	1	2



002

141,55 m - 193,55 m (L1)



Example: Entry of BC1

- Long Tunnel
 - All electronics inside
 - Limited space
 - Mixture of Trades
- Using KDS as a planning tool
 - All cables have to be specified
 - Orders are generated
 - Documentation is ready when cables are installed.



3Lab InKind Contribution: BPM System

3 types of BPMs

- Button BPM for different beam pipes
- Cavity BPM for 2 beam pipe diameters
- Reentrant Cavity BPM 30% of cold LINAC


Build by 3 Lab Collaboration


- CEA: Reentrant Cavity BPM + RFFE
- PSI: Entire Electronics, except Reentrant RFFE
- DESY: Entire Mechanics, except Reentrant Body

Readout

- MBU (Modular BPM Unit)
 - ➔ 4 Button BPMs
 - ➔ 2 (Reentrant) Cavity BPMs,
 - ➔ 1 Cavity + 2 Buttons
- Connection to DOOCS via a FPGA-FPGA Bridge with optical fibers. Up to 4 MBU connect to 1 DAMC02 interface board.
- Timing: Decoding XFEL timing protocol (via fiber) in the MBU
- Ref. Frequency (Cavity only) 216 MHz





More Details, Specs and Performance: to be presented by Boris






Delivery of cold BPMs for module assembly established:


- Production of BPMs finished
- First assemblies with both types successful
- Stock building of BQU for module production done
- Assembly of BQU for modules possible any time on request.






■ BPM System on Schedule

- Prototype tests @ FLASH all types successful
- All BPMs in house. Series production finished
- Electronics development has reached and even exceeded specifications.
- Pre-series of Cavity BPM system (Pickup by DESY and electronics by PSI) and is installed at FLASH II. Operation starts in KW17.




Example Production Process: BPME Cavity BPM for the Undulator Sections




- Goal: robust high performance BPM, suited for mass production.
- No individual tuning foreseen
- Starting point: SACLA design by T. Shintake
- First prototype @ 4.4 GHz
- Design adapted to XFEL frequency 3.3 GHz
(in Agreement with Electronics Development)
- RF simulation and mechanical design at DESY
- Prototypes in DESY workshop
- Beam tests at FLASH and PSI injector
- Industrialization; Qualify companies (painfull)
- Tender process (European)
- Pre-series 2 x 9 BPMs (perfect quality from two vendors)
- Series production with extensive QA support from DESY
- Finally 140 BPMs in spec.
- **Similar Procedure for Beamline Cavity BPM**
Series of 30 BPMs finished successfully




Series production of Undulator Cavity BPMs





- DESY provided a system to measure RF properties at FMB Berlin observe status of BPM fabrication at each step:
 - before brazing,
 - after brazing and
 - after welding of feedthroughs
- A measurement takes few minutes with additional analysis
- Measurement results send to DESY for revision and to get permission for next step.
- Delivery of BPMs in small lots after final production each, final measurement at DESY for acceptance.
- Additional acceptance Tests; Leak Check, RGA and Particle Cleanliness



Series production of Undulator Cavity BPMs





- After some pieces we observed a larger frequency variation at the reference resonator after brazing (still in spec)
- Production stopped, Investigation, Counteraction fixed, Production continued.




Larger resonance frequency difference before and after brazing is correlated with brazing material getting into the resonator;

counteraction increase brazing foil inner diameter




Dipole resonator	3295.4 ± 1.6 MHz 69.3 ± 1.1
Reference resonator	3301.3 ± 5.4 MHz 75.5 ± 1.2
Difference of Resonance frequencies	6.4 ± 4.7 MHz




Except of the Cold BPMs produced by industry, 3 further types are produced in house, using a High Precision Machine (OKUMA)




- BPMA: working horse 40,5 mm beam pipe (220 on stock)
- BPMD: 96 mm beam pipe for Dumps, Switchyards
25 have been produced
- BPMW: BPM before the dump window (200 mm);
all 3 items are available
- All feed-throughs delivered;
Custom Development together with Industry (VACOM).
- Cleaning and final Assembly in House (ISO5 Cleanroom)



BPM Production at the DESY Workshop

2 h/ BPM in 1.4429











■ Current Transformers or Toroids

- Network of monitors to interlock on transmission and bunch pattern failure
- Noise < 1 pC
- Electronics still in development
- Vacuum hardware and most of the Front-End Electronics ready
- 4 pickups and prototype front ends installed in FLASH II

■ Dark Current Monitor

- Cavity based
- Measure dark current and bunches
- Sensitivity about 10 nC (DC), 100 fC (bunched)






■ Screen Stations

- Scintillator based, Spatial suppression of COTR
- On Axis, Off axis screen plus calibration target
- Uses “Scheimpflug’s” Principle to extend depth of field
- Big chip 4 MP CCD with GigE interface
- 10 μm resolution, sensitivity sufficient for about 50 pC (single bunch, streaked, shown at FLASH)
- About 60 stations, 12 with off axis screens
- Vacuum hardware in house, final assembly started
- 4 XFEL type stations installed at FLASH II

■ Wire Scanners

- Triggered fast scanner with 1 m/s speed, slow scans also available
- Separated horizontal and vertical units
- Full profile within a macro-pulse
- Vacuum hardware to be delivered house, remaining components ordered
- Detector development going on

Beam Size Measurement: Hot Spots






Section	Screen	Screen Off Axis	Wire-scanners (WS)
Injector	5	4	0
BC1	3	4	0
BC2	6	4	0
Collimator	7		3
Beam Distribution	5		
Undulator Lines	11		3 x 3
Chicanes	3		
Dump	6		
Photon	3		
Total	49	12	12


XFEL uses Screens and fast Wire Scanners

- to check and detect beam at critical places
- to match the optics and to measure emittance at
 - Injector (Screen)
 - Bunch Compressor B1 and B2 (Screen)
 - after the LINAC (Screen/WS)
 - before the undulators (Screen/WS)
- to measure slice parameters in combination with a transverse mode structure in
 - Injector
 - Bunch Compressors B1 and B2

XFEL Screens: Optics Design Record On-Axis and Off-Axis Profiles



Basler Aviator avA2300-25gm
2330 x 1750 pix, 5.5 µm
Monochrome, GigE




f = 180mm for 1:1





f = 120mm for 1:2

Large Area Photo Macro Lenses
from Schneider Kreuznach






FLASH II Installation

XFEL Screens: Resolution Measurement and System Performance



Resolution map of the Optics using the build in calibration target. The “tilt axis” goes from left to right.



CCD-Camera:

Gain: 330


$t_{exp} = 94556 \mu\text{sec}$

Beam:

Single-Bunch



$Q_b = 500 \text{pC}$

$f_{rep} = 10 \text{Hz}$




Beam spots moved by a dipole along the “tilt axis” to different positions on the screen

Picture on the right shows the overlay of the single pictures.





Location of Wire-scanners @ XFEL



- Slow and fast scans (1 m/s) possible
- Fast Scan on trigger (Jitter < 10 μ s) within one bunch train
- Max. 100 bunches/train should hit the wire
- Detector and Scanner weakly coupled (by DAQ)
- BLM suited as additional detectors
- WS planned before collimator and before each undulator
- Vacuum ports foreseen also in the BC's (COTR)
- Mechanics ordered; ready Q1/2014






Wiresscanner: Block Circuit



Remarks

- Power and Matchbox in same Rack with uTCA Crate housing the DAMC2/RTM
- distance between Scanner and Powerbox limited by length of Heidenhain Interpolator cable (20m)
- cables and connectors to be defined (?)
- positions of the components in the Powerbox to be defined
- height of Powerbox 5HE

T.Lensch, 31.5.2013





- **BLM: Beam Loss Monitors**
 - Based on Scintillators and Photomultipliers
 - μ TCA based with low latency MPS interface
 - Scintillators & Mechanics: Production finished at IHEP
 - Pre-series being installed at FLASH II
- **BHM: Beam Halo Monitors**
 - Diamond and Sapphire crystals used as „ionization chambers“
 - μ TCA readout similar to BLMs
 - Serious problem to get good diamond detectors.
 - System for the injector ready for installation



Dosimetry:

- Gamma and Neutron sensors
- FMC board integrated on MPS board
- Distributed system in electronics racks
- Bus system with external sensors for undulators
- Final prototyping phase

Beam Loss Monitor System for XFEL





~300 Beam Loss Monitors
(More than half – in undulator area)



DAMC02 with custom RTM

- Comparator, ADC, Alarm Generator
- Test Pulse Driver
- Supply for Cockcroft Walton Generator
- Prototypes in test
- Pre-series for FLASH II in Production

BLMS: Production of Housings and Scintillators @ IHEP Protvino




Test unit for scintillator test. The black cap houses beta source (Sr^{90})



scintillator




QA of mechanics after delivery



Picture from the irradiation facility at IHEP; Radiation Damage Tests




The radiation monitoring system



External Sensors 0.1 Gy – 2 kGy; up to 10 kGy => reduced resolution


Scalable
frontend :

- # of channels
- # of readout modules
- cabling




Total: 540 external sensors + 330 internal sensors

Realization – system components & setup




DESY AMC2 (μ TCA) FMC Carrier in BPM MBU



Dosimetry mezzanine card (FMC) on AMC motherboard for the Machine-Protection-System (MPS) carries dosimetry for measurements inside shielded electronic racks

Frontpanel interface allows connection of external dosimetry sensors (DAMC02 only)


Sensor chip (γ)



Undulators get milled notches to House RadFet sensors.



Frontpanel interface of AMC board conducts undulator dosimetry signals



- Focus of the talk was on items produced in bigger numbers
- Nothing reported on
 - Special OTR stations for the BC and dumps
 - (start production of vacuum vessels soon)
 - Mechanics Contributions for WP-18
 - E-BPM (start production of vacuum vessels soon)
 - and BAM mechanics (ready)
 - Beam Halo Monitors
 - Diamond Detectors used as ionization chambers using adapted BLM electronics
 - Serious problems to get the diamonds with required quality (electric strength worse than previously delivered sensors)
 - Gun diagnostics (clone of recent PITZ/FLASH design)
 - HOM based BPM Phase Monitor development for 1.3 GHz and 3.9 GHz systems

Thanks to all colleagues contributing to the work presented here:

- W. Decking
- C. Simon
- B. Keil
- M. Pelzer
- S. Vilcins
- C. Wiebers
- M. Werner
- I. Krouptchenkov
- A. Kaukher
- M. Holz
- J. Lund-Nielsen
- N. Baboi

- H. Tiessen
- T. Lensch
- F. Krivan
- A. Delfs
- R. Neumann
- N. Wentowski
- D. Lipka
- M. Yan
- M. Drewitsch
- I. Kundoch
- D. Bandke

- V. Gharybian
- G. Kube
- K. Wittenburg
- F. Schmidt-Föhre
- N. Baboi
- J. Kruse
- C. Behrens
- R. Susen
- P. Smirnov
- J. Neugebauer
- Z. Pisarov