

# PETRA III Operation

30th ESLS Workshop,  
ESRF Grenoble,  
December 14, 2022

**Michael Bieler**

for the PETRA III / PETRA IV Team

Thank you for the support and discussions:

R. Wanzenberg, M. Schaumann, G. Kube, D. Haupt,  
H. Ehrlichmann, J. Keil, G. Sahoo, R. Onken, R. Bartolini.



# Contents

- **Operation, Availability & Failure Analysis for Feb-Dec 2022**
- **PETRA-IV studies at PETRA III**
- **Energy saving options and studies**
- **Upgrade plans, PETRA IV**

# 4640 h of User Time Delivered 16.2. – 12.12.2022

144 h more planned between 13.12.-18.12.2022


Statistics: 01.01 – 12.12.2022



# 2022: Availability of 98.3%

MTBF: 57.3 h  
MTTR: 1 h

Few major failures and troublesome period of 2 weeks after summer shutdown



W12: Power Glitch (duration 3h30)

W18: Faulty triggers of injection kicker (duration 4h05)

W27: Main power station B over-voltage problem (duration 16h20)

W34-35: Several independent failures:



- Power supplies
- Top up stops
- Cavity trips
- Cooling water
- Vacuum at experiments

# 5 Weeks of User Run remain in 2022

3 days of PETRA IV study time before winter shutdown

Studies/Commissioning	A (A)
Test run	tr
No operation	A (A)
User run	
Working day	
Saturday	
Sunday/ Bank holiday	

	January 2022	February 2022	March 2022	April 2022	May 2022	June 2022	July 2022	August 2022	September 2022	October 2022	November 2022	December 2022
1		IE NG	multi β StrS	SRI IB tr	40	A	multi β	A R	40	multi	40	multi
2		IB	β	tr	40	A	multi β	A R	40	multi		multi
3	A	IB	multi β StrS		40	A	multi β	A R	40			multi
4	A	IB	multi β StrS	40	A		multi β	A R	40			multi
5	A	IB	multi β	40	40		multi β	A R	A			multi
6	A		multi β	40	40		A		A			multi
7	A	IB	multi β	40	40	IB	multi	A	A			A
8	A	IB	multi β	40	40	tr	multi	A R				multi
9	A	A IB tr	A	40	40		multi	A R	IB tr			multi
10	A IEV	IB tr StrS	40	40	40		multi	IB	tr			multi
11	A IEV	IB tr StrS	40	40			multi	IB	tr			multi
12	A		40	A	40		multi	IB	multi			multi
13	A	tr	40	A	40		multi	tr / IB	multi			multi
14	A IEV	tr StrS	40	A	40		multi	tr	multi			multi
15		tr StrS	40		40		multi	tr	multi BetrFest			multi
16		multi StrS	40		40		multi	40	multi			multi
17	IMV	multi StrS	40		40		multi	40	multi			multi
18	NG	multi StrS	40		A		A R	40	multi			IB tr β
19	NG	multi	40		IB		A R	40	multi			tr β
20	NG	multi	40	tr IB	40		A R	40	multi			tr β
21	IEV NG	multi StrS	40	40	40		A R	40	A			multi β
22		multi StrS	40	40	40		A	40	multi			multi β
23		A β	40	40	40		A	40	multi			multi β
24	IM	multi β StrS	A SRIprep	40			A	40	multi			multi β
25	IM	multi β StrS	A SRIprep	40			A R	40	multi			multi β
26	IE NG	multi β	A SRIprep	40			A R	40	multi			multi β
27	IE NG	multi β	A SRIprep	40			A R	40	multi			multi β
28	IE NG	multi β StrS	A SRI	40			A R	40	multi			multi β
29			A SRI	40			β	40	multi			multi β
30			SRI IB	40			multi β	40	multi			A
31	IE NG		SRI IB		40		A	40	multi			



Girder movement experiment in Max von Laue Hall.


Shortest possible winter shutdown:

→ 4896 h of user run scheduled

Summer shutdown:  
Repair of cooling tower

# 3 Days of Study for PETRA IV Girder Alignment System

Girder Movement Test in PETRA III Max von Laue hall planned for 19.-21.12.2022



## PLAN

Move **ONE** girder in Max von Laue hall with the remote-controlled motors up to  $\pm 300 \mu\text{m}$ .

## GOALS

- Study girder movement to orbit correction response
- Input for design of PETRA IV automatic girder alignment system
  - Identify technical requirements and limitations
  - Gaining experience and confidence in remotely moving girders
  - Development of required procedures for PETRA IV

## CHALLENGES




Girder alignment system **not intended for movements** after the initial installation phase of PETRA III (2009)

- Fixed vacuum joints** between girders
- System **unused** and not connected since 2009
- Movement and verification **procedure not performed for many years.**

# Successful Dry Run for Girder Movement Test on 19.10.2022

Initial tests confirmed practicability & accuracy of planned procedure

- Laser tracker and dial gauges measured the movement.
- Input of **signs and units** have been crosschecked.
- **Accuracy** of requested position within  **$\pm 20 \mu\text{m} - 30 \mu\text{m}$**  (peak-to-peak).
- For only transverse movement (no rotations, longitudinal fixation) **starting position is recovered** within the same accuracy.




Free standing test girder in survey lab

Motors installed on support feet with dial gauge measuring vertical movement

Analysis of dry test and planning of tunnel test are ongoing.

# PETRA VI Prototype Test Program continues in PETRA III

Successful preparation and installation work ongoing



Installation work during summer shutdown Jul/Aug 2022 in South Right (SR).

- **SR cavity section** had to be **vented**
- New beam pipes and valves installed
- Preparation for the PETRA IV prototype cavity (installation in coming winter shutdown).
- Installation of two current monitor types.



WP 2.12:  
RF Systems

WP 2.05:  
Diagnostics





# Progressing Studies of PETRA IV Diagnostics

G. Kube

BPM electronics and Beam Current Monitors are being tested

## BPM electronics performance study at PETRA III

Evaluation of long term drifts with e.g. 40 bunches @ 100 mA



accelerator tunnel  
electronics cabinet




Libera Brilliance+

G. Kube et al., Proc. IBIC 2022, Krakow (Poland), 11.-16.9.2022, WEPO8

Well within specifications  $< 1 \mu\text{m}$

## New Diagnostic Section in PETRA III

Test section ( $\varnothing$  60mm) installed in PETRAIII SR during summer shutdown (July/August 22)



- ➔ FCT developed small vacuum leak  
➔ removed 21.9.2021
- ➔ Further improvements planned

Bunch current measurement

DC current measurement



# Low Beam-Energy Operation could Reduce Energy Consumption

**PETRA III: ~85% of the energy is consumed by magnets and RF**

## Options to reduce energy consumption for the PETRA III complex:

- Increase time between top up injections, meanwhile **switch off injectors**
  - *Test beam operation at DESY-II*
  - *Operationally challenging if LINAC is not in thermal equilibrium, degradation of reliability expected*
- Reduce RF power consumption by reduction of **beam current** and/or **RF voltage**
  - *needs optimization of working point*
- **Reduced energy operation**
  - *operation @ 5 GeV could save ~20%*
- Extend shutdown periods (no beam operation)



# 5 GeV Operation with 480 Bunches seems Feasible

Lifetime Reduction at 5 GeV prevents 40 Bunch Operation

## Achieved Beam Performance

PETRA III	Standard Parameter	Studien 09.09.2022
Strahlenergie / GeV	6	5
Emittanz / pm rad	1300	ca. 850
HF Spannung / MV	19	15
<b>Multibunch Mode</b>		
Anzahl der Bunche	480	480
Strahlstrom / mA	120	100
Strahllebensdauer / h	10	3.5
<b>Timing Mode</b>		
Anzahl der Bunche	40	
Strahlstrom / mA	100	
Strahllebensdauer / h	1.5	

Tests done with 480 bunches, 100mA for 2 days

*Significant lifetime reduction at 5 GeV observed*


→ *Expected lifetime with 40 bunches too low for reasonable operation*

Reduction of **emittance** confirmed:

- *Horizontal emittance*: theoretical 750 pm rad  
measured ~800 pm rad  
@ 6 GeV, ~1300 pm rad
- *Vertical emittance*: uncertain  
(limitation of measurement)

# 5 GeV Operation Requires ~1.5 MW less Power than 6 GeV

This corresponds to ~20% of the used power of the whole PETRA III complex



Energy saving potential of reducing the beam energy from 6 GeV to 5 GeV:

→ ~25% only PETRA III


→ ~20% all PETRA III complex

Based on data taken

- 6 GeV: 15.08.2022 09:55
- 5 GeV: 09.09.2022 12:35

# Drastic Reduction of High Energy Photon Intensity at 5 GeV

Successfully delivered 22 h of 5 GeV Test Run to Beamlines



Calculation for photon beam brilliance  
at PETRA III 5 GeV vs. 6 GeV

## Observations

Photon energies

- $2 < E < 5$  keV a **small increase** of intensity, factor 1.25
- $8 < E < 20$  keV: **losses of factor 2 to 5**
- $E > 20$  keV: **losses of factor 10**

## Conclusion from beamlines

- Almost all beamlines would suffer
- Loss for beamlines vs. saving is unreasonable
- **5 GeV is NO option for the user run.**

# Injectors Power Consumption Reduced by up to 150kW

Further options are being investigated

H. Ehrlichmann  
D. Haupt

## Implemented measures:

- Reduction PIA energy 450MeV → 400MeV: -25 kW
- Switch off LINAC-II redundancy ( $\leq 5/12$  klystrons off):  $-5 \times 25 \text{ kW} =$  -125 kW  
→ *no hot-spares, could influence availability*

---


- 150 kW

## Measures under investigation:


- Reduction DESY-II peak cycle energy 6.3 GeV → 6.0 GeV ???  
→ *Negative for test beam users: need high energies*
- Optimization of klystron working point: ???
- Reduction LINAC-II rep-rate 50Hz → 10Hz ???  
→ *Influence on PIA accumulation*

# Draft Schedule for 2023 foresees 4992 h of User Time

Installation of new undulator and PETRA IV test cavity




- Installation of
- Undulator for PU25 (Ada Yonath hall)
  - Test cavity for PETRA IV



# PETRA III is one of the core facilities at DESY

Each year ~5000h users operation serve more than 2000 users




Parameter	PETRA III
Energy [GeV]	6
Circumference [m]	2304
Emittance (hor./vert.) [nm]	1.3 / 0.013
Total current [mA]	100

## PETRA IV project:

replacing PIII with an ultra low emittance ring (20 pm) adding a new Experimental Halls in two more octants



# From PETRA III to PETRA IV




**Eight Arcs (45°), 201.6 m long**

One arc build from 9 **DBA cells**  $L_{\text{cell}} = 23 \text{ m}$ , 5 m ID straight sections  
5 pure FODO-arcs + 2 modified FODO arcs with 2 **DBA cells**

## Beamlines

Max von-Laue Hall:14; PXN:5; PXE: 7

→ **20 pm**



**Eight Arcs (45°), 201.6 m long**

72 cells ESRF-EBS **H6BA cells**  
9 cells per arc  $L_{\text{cell}} = 22.75 \text{ m}$ , 4.3(TBC) m ID straight sections




## Straights for Beamlines

Max von-Laue Hall: 9; PXN: 3; PXE: 3 + New Hall: 9 + 9(8)

# PETRA IV accelerator lattice

The PETRA IV accelerator lattice fulfills all the requirements to produce X-ray beams with unprecedented brightness. PETRA IV will be the world leading machine.




The lattice is based on a novel cell structure (H6BA) that is replicated identical across all octants (72 cells) achieving 20 pm electron beam emittance with >10h beam lifetime and off axis injection.



# Engineering integration of the cell in progress (TDR)

Ongoing work:


- engineering integration of all components in the cell on the girders
- check on space envelope and clashes
- design of the extraction photon pipe
- implementation of the canted photon beamlines
- implementation of RF section
- implementation of services



# PETRA IV project schedule

The draft breakdown below hinges on

- Project approval in mid 2024
- Call for tender placed in mid 2024
- Dark period ~24 months
- First light in Jan 2029



# Conclusions

- PETRA III operates with high availability
- PETRA III supports development of PETRA IV with study beam time wherever possible
  - RF and diagnostics installations done in summer shutdown
- Beam operation @ 5 GeV could reduce the PETRA III complex power consumption by ~20%, however performance loss vs. saving potential seems unreasonable for beamlines and users.
- The PETRA IV project is in the TDR phase, approval in 2024?

**Thank you for your attention**

## Contact

**DESY.** Deutsches  
Elektronen-Synchrotron

[www.desy.de](http://www.desy.de)

Michael Bieler  
MBB  
[bieler@desy.de](mailto:bieler@desy.de)  
0049 40 8998 3805

# Comparison Energy Consumption: 6 GeV vs. 5 GeV

Main contributions are magnet current reduction and required RF power


Power consumption at 6 GeV vs. 5 GeV

	PETRA III 15.08.2022 9:55	PETRA III 09.09.2022 12:35	Differenz 15.08-09.09	relative Differenz
Energie / GeV	6	5	1.0	16.7%
Strahlstrom / mA	100	100	0.0	
HV-Spannung / MV	19	15	4.0	21.1%
<b>Leistungsaufnahme / kW</b>				
Geb 47c Sektoren	204.4	200.0	4.4	
Geb 47c Halle	314.4	282.0	32.4	
Geb 47 c Tunnelelektrote	156.0	163.8	-7.8	
<b>Geb 47 c Magnetstrom</b>	<b>135.2</b>	<b>94.0</b>	41.2	
<b>Sender SL</b>	<b>1614.1</b>	<b>1244.8</b>	369.3	
<b>Sender SR</b>	<b>1657.0</b>	<b>1173.0</b>	484.0	
<b>Magnete</b>	<b>1695.3</b>	<b>1131.0</b>	564.3	
<b>Summe PETRA III</b>	<b>5776.4</b>	<b>4288.6</b>	<b>1487.8</b>	25.8%
Vorbeschleuniger				
<b>LINAC II</b>	973.9	910.2	63.7	
<b>DESY Sender</b>	516.4	516.0	0.4	
DESY Magnete (geschätzt)	500.0	500.0	0.0	
<b>Total</b>	<b>7766.7</b>	<b>6214.8</b>	<b>1551.9</b>	20.0%



# Comparison Energy Consumption: 6 GeV vs. 5 GeV

## RF Voltage and Beam current scan



Power consumption of RF transmitter at 6 GeV with 480 bunches for different beam currents and RF voltages


PETRA III, 6 GeV, 480 Bunche				
21.09.22			Senderleistung	
Zeit	Strom/mA	Spannung/MV	P_SL/kW	P_SR/kW
16:00	80	<b>18.9</b>	1475	1408
16:05	80	18.1	1476	1409
16:10	80	17.1	1476	1408
16:20	100	17.1	1476	1408
16:23	100	17.9	1475	1409
16:26	100	<b>18.9</b>	1611	1521
<b>16:32</b>	<b>120</b>	<b>18.9</b>	<b>1610</b>	<b>1519</b>
16:36	120	18.1	1610	1521
16:39	120	17.2	1609	1520

# Power Consumption at DESY

15.08.2022, 40 bunches, 100 mA (Reference)

<http://cssweb.desy.de:8084/sdsweb/display/LastmanagementVariant>

e1



# PETRA III is Study Framework for PETRA IV Development

Diverse studies involve several groups and work packages

WP 1.12:

Accelerator Foundation

WP 1.01:

Civil Construction

WP 2.01:

Accelerator Physics

WP 2.07:

Alignment

WP 2.10:

Accelerator Controls

WP 2.04:

Vacuum Systems

WP 2.12:

RF Systems

WP 2.05:

Diagnostics

## Beam stability concepts

- Monitoring of environmental parameters
- Evaluation of ground vibrations
- Orbit analysis
- Modelling of data
- Girder movers

## Accelerator physics / beam dynamics

- Test of commissioning strategies
- High level software
- Test of algorithms
- Impedance model

## Technical subsystems

- RF system
- Diagnostics

## Selection of studies planned for 2022

Implementation of *alternative methods* to measure optics, chromaticity and coupling

Impact on orbit when *moving a girder* (December 2022)

*Vibrations* due to civil construction (mid 2022)

Installation of *diagnostic* components: Current monitor, BPM (summer shutdown 2022)

Preparation for PETRA IV *test cavity* (installation in 2023)

For a more complete list see back-up slides

# Diverse Studies at PETRA III support PETRA IV TDR

## PETRA IV resources support studies at PETRA III

### Performed 2021

Truck movement → impact on orbit

Correlation of temperatures with mechanical measurements in the tunnel

Correlation with orbit data

First turn threading, test of software interface

Collaboration with SLAC  
robust conjugate direction search (RCDS)

Collimator wakefields

Installation of waveguides for the cavity test  
Preparation for the solid state amplifier

Test of new BPM electronics (new Libera hardware)  
Diagnostic test with 2 ns bunch filling pattern

### Planned for 2022

Implementation of faster methods for optics, coupling and chromaticity measurements

Development of machine learning tasks

Test to move a girder → impact on orbit

Vibration test for PXW Hall construction

Installation of a solid state amplifier

Preparation for the installation of a single Cell 500 MHz PETRA IV cavity

Installation of diagnostic components:  
Current monitor, BPM  
(summer shut down 2022)

Curing of crack between tunnel segments in SWR 37

Installation of cavity postponed to 2023, due to delayed delivery of components