11<sup>th</sup> Radsynch, May 30 – June 2, 2023

# Shielding Design and Current Status of New Compact Synchrotron Facility at PAL

### Hee-Seock Lee<sup>1,2</sup>, Mahdi Bakhtiari<sup>2</sup>, Ukjae Lee<sup>1</sup>

<sup>1</sup>Radiation Protection Team & 4GSR Radiation Shielding Analysis Team, Pohang Accelerator Laboratory (PAL), POSTECH, Korea <sup>2</sup>Division of Advanced Nuclear Engineering, POSTECH, Korea

lee@postech.ac.kr

### Contents



- 1. Introduction of PAL-EUV Project and its Current Status.
- 2. Radiation Shielding Design Criteria
- 3. Methods and Interesting Issues at Radiation Shielding Analysis.
- 4. Shielding Analysis
- 5. Radiation Safety Control System
- 6. Commissioning Status and Radiation Control
- 7. Summary

### Light Sources at PAL (Project years)



PLS II (2009-2011)

Full energy linac

3 GeV, 400 mA, 282 m

PAL-XFEL (2011-2015) 11 GeV, 60 Hz, 1.1 km

> PAL-EUV (2020-2022) 400 MeV, 140 mA, 36 m 20 MeV linac + Booster

Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

#### Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

### 1. PAL\_EUV Project overview

- PAL-EUV is a new Low Energy Synchrotron Light Source, fully funded from Korean Government
  - > To provide diffraction-limited radiation at EUV range
  - Application mainly for semiconductor R&D
  - Construction project from March 2020 to December 2022
  - Project budget 29 Billion Korean Won (~21 Million US Dollar)
    - 20 Billion Won for accelerator
    - 9 Billion Won for beamline (mask inspection)







EUV Lithography is the current and future solution for semiconductor patterning technology.
 PAL-EUV is dedicated infrastructure for the EUV materials and process research.



INTERNATIONAL ROADMAP FOR DEVICES AND SYSTEMS (2020 EDITION LITHOGRAPHY)

Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

### 1-1. Project Overview – Building Renovation





Originally "Components Storage & Assembly Building" used for PLS-II upgrade → PAL-EUV Building (since 2020)

Hee-Seock Lee, 11<sup>th</sup> Radsynch, ESRF, May 30- June2, 2023

### **1-1. Project Overview – Building Layout**





### **1-2. PAL-EUV Accelerators**

PAL 포항가속기연구소 POHANG ACCELERATOR LABORATORY

□ Injector Linac (to 20 MeV)

- Photocathode gun (in-house, 2.7 MeV) + 3 m accelerator column
- 10 MW S-band klystron + solid state modulator
- □ Booster Ring(from 20 to 400 MeV)
  - 2 straights for injection/extraction
  - 500 MHz PLS cavity (reuse)
- □ Storage Ring(400 MeV)
  - 4 straights for injection and three IDs
  - 500 MHz RI cavity
  - 1500 MHz harmonic cavity



### **1-2. PAL-EUV Accelerators – Linac**

Electron Beam at Linac End

- Beam energy : 20 MeV
- Bunch charge : 35 ~ 300 pC
- Transverse normalized emittance : 0.5 mm mrad
- Bunch length : 2 ps rms







🕖 포항가속기연구소

POHANG ACCELERATOR LABORATOR

### **1-2. PAL-EUV Accelerators – Booster & Storage Ring**



- Beam energy : 400 MeV
- Circumference : 22.2 m
- Emittance : 4.2 nm
- Repetition rate : 0.5 Hz

#### □ Storage Ring

Beam energy : 400 MeV

포항가속기연구소

OHANG ACCELERATOR LABORATOR

Ъ

Stored current : 140 mA

----

Circumference : 36 m



### 1-2. PAL-EUV Accelerators III – Booster & Storage Ring



Parameters	Values at 400 MeV
Circumference	36 m
Harmonic number	60
Beam current	140 mA
Emittance_X (nm)	1.16
Tune_X	7.153
Tune_Y	3.044
Chromaticity X, natural	-10.66
Chromaticity Y, natural	-16.71
Chromaticity X, corrected	1.0
Chromaticity Y, corrected	1.0
Alpha	0.0104
dE/turn (keV)	1.7
Energy spread (E-4)	3.82
Damping time X (ms)	30.7
Damping time Y (ms)	56.7
Damping time S (ms)	49.0





Vacuum model of PAL-EUV accelerator



### 2. Shieldign Design Criteria : Control Policy at PAL



### Dose Limit (based on Korean Regulation)

- Radiation Workers (RW): 20 mSv/y
- Frequent Visitors : 6 mSv/y
- Public (including User) : 1 mSv/y
- Site Boundary : 0.25 mSv/y

- Shielding Criteria (Normal Operation)
  - RW accessible area : 10 mSv/y,

 $(\frac{1}{2}$  of dose limit based on ALARA)

- User accessible area : 1 mSv/y

#### (Abnormal Operation)

1 mSv for single event

#### Area Classification

- Restricted Area :  $0.25 \text{ mSv/y} \le \text{Dose} < 1 \text{ mSv/y}$
- Generally-Controlled Area : 1 mSv/y ≤ Dose < 20 mSv/y
- Radiologically-Controlled Area :  $20 \text{ mSv/y} \leq \text{Dose} < 1 \text{ mSv/h}$
- High Radiation Area : Dose  $\geq$  1 mSv/h (No Access)





PAL 포항가속기연구소

POHANG ACCELERATOR LABORATORY

#### Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

□ To use PHITS3.30 to design real shielding structure

- Normal / Abnormal Op.
- One shielding door equivalent to concrete wall
- Neglecting lower energy linac in the one region
- Safety Permanent Magnet for beam line shielding (Safety PM was not needed at PLS-I & -II)
- Error of magnetic field simulation at old version of PHITS

3rd undulat



Track Detection using [T-track] tally

no. = 1, ie = 1, iy = 1

PHITS3.32

calculated by PHITS 3.3

### □ To use SHIELD 11 to decide thickness of accelerator tunnel wall & ceiling

- Side walls for controlled area : 40 cm Ordinary Concrete.
- Side wall for public area : 60 cm Ordinary Concrete + Extra Pb
- Ceiling for RC area : 10 cm Ordinary Concrete + (Extra Pb for abnormal op.)

1st undulator (Und1, 13.5 nm

500 MHz main cavit

Tune & feedbac

### 3. Methods and Interesting Issues at Radiation Shielding Ana No 프랑가속기연구

plotted by AnGeL 4.50

Date = 09:08 24-Mav-2023

### **3-1. Methods in Radiation Shielding Analysis**

- □ Shielding Calculation Strategy of PAL-EUV
  - One wall meets out of building, public access zone.
  - Shielding Criteria : 0.5 uSv/h, 5 uSv/h, 1 mSv/event
  - Calculation tools : (SHIELD11), PHITS
  - Beam loss scenario : Assumed from experts' experience
  - 20 MeV linac is not impact machine in the view of RP
- Normal Beam Loss
  - Beam loss at each injection process (0.5 Hz)
  - Uniformly-distributed loss at Booster (400 MeV)
  - Uniformly-distributed loss at SR
  - Assume thick iron target (10Xo) at each dipole magnet
- □ Accidental Beam Loss (Abnormal Operation)
  - Total loss of stored beam
  - Continuous loss at one point during injection
  - Beam loss by failures of magnets for injection or dipole magnets



Storage Ring Parameters for PAL EUV	
Beam energy [MeV]	400
Beam current [mA]	140
Beam life time [min]	30 (1800 s)
Circumference [m]	36
Stored charge [nC]	16.8
Stored electron	1.05×10 <sup>11</sup>
Stored energy [J]	42
Beam loss (pC/s)	16.8/(1800) = 9.33
Beam loss (e/s)	5.83×10 <sup>7</sup>



### **3-2. Methods – Normal Beam Loss**



- 1. Dose rate from distributed loss of stored beam in storage ring  $\rightarrow$  [20pC/injection is lost during 2 seconds]
- 2. Dose rate during the injection from booster to storage ring  $\rightarrow$  [5% loss locally+ 5% distributed loss in SR]
- 3. Dose rate from distributed beam loss during boosting  $\rightarrow$  [20% distributed loss]
- 4. Dose rate during the injection from linac to booster  $\rightarrow$  [10% loss locally+10% distributed in Booster]





### 4. Radiation Shielding Analysis using PHITS code

- □ Accelerator Conditions
  - Good injection efficiency (90% B to SR)
  - Mild loss during boosting (20% loss but 400 MeV)
  - Relatively low beam power (140 mA, 1.05 x 10<sup>11</sup> e-, 0.5 Hz injection rate)

U What is beam loss condition with no detail information from Accelerator group

- All bending magnets is normal beam loss point for distributed loss
  - → Loss at thick target (Φ8 cm x 17.6 cm Iron)

Beam direction is the same to normal beam direction

- Any bending magnet failure is assumed for abnormal op.
  Thinner target (2 cm-thick Iron) for beam line shielding
- Injection failure is also assumed as failure of first bending magnet after injection
- The most accidental case 400 MeV electrons go to beam line, experimental hall.





### 4-1. Final Results of Main Radiation Shielding Structure

- □ Main Shielding Structure
  - Side wall: 40 cm O.C. or 60 cm O.C.
  - Ceiling : 35 cm thick O.C. removable panels (Structural requirement, a few cm Fe is sufficient for area control)
  - Shielding Door : Pb (40 mm)+ HPDE (120 mm) + Steel 4.2 mm

40 cm thick concre

90e 112 4300

------

60 cm thick concrete

.

Additional shielding for public zone 

10

0



Concrete ceiling blocks



40 120 10

10 200

10

Sliding shielding door







#### Radius $: 3 X_{m} (4 cm)$

- Beam loss : 20 pC/injection=10 pC/s
- Thickness : 10 X<sub>0</sub> (17.6 cm)

• Target







East

North

### Distributed loss of stored beam in storage ring (2/5)-Flux







### Distributed loss of stored beam in storage ring (3/5)- Dose

Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

22



#### Hee-Seock Lee, 11<sup>th</sup> Radsynch, ESRF, May 30- June2, 2023

23



# Distributed loss of stored beam in storage ring (5/5)- Dose

Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

포항가속기연구소

POHANG ACCELERATOR LABORATORY







#### 27

Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023







Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

30



### 4-2 Beamline Shielding Analysis: 3D view of the Experimental Hutch



\* 1 Air \* 2 Concrete \* 3 Iron \* 4 Lead \* 5 PE \* 6 STS304 \* 7 soil





#### Hee-Seock Lee, 11<sup>th</sup> Radsynch, ESRF, May 30- June2, 2023

### Beam line: Normal operation-Dose-Vertical view-YX





**Neutron dose** 

33



PAL 포항가속기연구소

POHANG ACCELERATOR LABORATORY

### 5. Radiation Safety System – Area Monitoring System

#### Locations





#### **System Configuration**



# EUV Radiation Monitoring System

포항가속기연구소

POHANG ACCELERATOR LABORATOR







Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023

35

### 5. Radiation Safety System – Personnel Safety & Interlock Sy

Main Sequence System (PLC-based)

#### **PSIS Configuration**



Hee-Seock Lee, 11<sup>th</sup> Radsynch, ESRF, May 30- June2, 2023

### 6. Commissioning & Radiation Control

- □ At present, Commissioning of Booster Synchrotron
  - Linac commissioning started at Feb. 1<sup>st</sup>.
  - 280 MeV is achieved at May 15<sup>th</sup>.
  - Commissioning will be finished before August.
  - User service is planned to start at late 2023.







### **Radiation Control Example**



# EUV-4 (outdoor, public zone) Dose level



# EUV-5 (2F) Dose level



### 7. Summary



- New compact synchrotron radiation facility (PAL-EUV) was launched for EUV industrial application
- □ Radiation Shielding Analysis was carried out by PHITS3.30.
- □ After getting operation permit, the commissioning is in process.
- □ The analysis results will be confirmed in the commissioning period.
- Upcoming issues
  - Installing Safety Permanent Magnet for beam line shielding (after updating PHITS version)
  - Radiation level control at 400 MeV for Booster & Storage Ring
  - New beam line structure (Modified & Additional branch lines)









## **Thank You for Your Attention!**



Hee-Seock Lee, 11th Radsynch, ESRF, May 30- June2, 2023